

Prescriptive Packages 5000 Degree-Day Region

Multiple-Family

Package	Maximum		Minimum						Heating/Cooling Equipment Efficiency ⁹	
	Glazing Area Percent ¹	Glazing U-Value ²	Ceiling R-Value ³	Wall R-Value ⁴	Floor R-Value ⁵	Basement Wall R-Value ⁶	Slab Perimeter R-Value ⁷	Crawl Space Wall R-Value ⁸		
1	12%	0.55	19	11	13	0	4	0	High Heating	UCC Basement Tradeoff
2	12%	0.35	13	11	13	0	4	0	High Heating	
3	15%	0.55	19	11	19	0	4	0	High Heating	
4	15%	0.35	13	11	11	0	4	0	High Heating	
5	18%	0.55	19	11	13	0	4	0	High Heating	
6	18%	0.35	19	11	11	0	4	0	High Heating	
7	20%	0.55	30	15	19	0	4	6	High Heating	
8	20%	0.35	19	13	13	0	4	0	High Heating	
9	15%	0.70	38	13	11	5	0	6	Normal	Basement Wall Tradeoff Not Applied
10	15%	0.60	26	11	11	5	0	5	Normal	
11	20%	0.60	26	13	19	9	4	15	Normal	
12	20%	0.50	26	11	13	6	0	7	Normal	
13	25%	0.50	38	13	15	7	2	10	Normal	
14	25%	0.45	38	13	11	5	0	6	Normal	
15	30%	0.40	49	13	11	5	0	6	Normal	
16	15%	0.90	19	11	11	5	0	6	High Heating	
17	20%	0.75	26	11	11	5	0	7	High Heating	
18	25%	0.70	30	13	15	7	2	13	High Heating	
19	25%	0.65	30	13	11	5	0	7	High Heating	
20	30%	0.60	30	13	15	7	2	14	High Heating	
21	30%	0.55	26	13	11	5	0	8	High Heating	
22	15%	0.90	30	11	11	4	0	5	High Heat/Cool	
23	20%	0.75	26	11	11	5	0	6	High Heat/Cool	
24	25%	0.65	30	11	11	5	0	7	High Heat/Cool	
25	25%	0.60	26	11	11	5	0	7	High Heat/Cool	
26	30%	0.60	38	11	19	8	2	19	High Heat/Cool	
27	30%	0.55	38	13	13	6	0	10	High Heat/Cool	