

ENVIRONMENTAL ASSESSMENT

Prepared pursuant to:
NATIONAL ENVIRONMENTAL POLICY ACT

For:
TREMLEY POINT CONNECTOR ROAD
and
PILE CREEK WETLANDS MITIGATION
Borough of Carteret, Middlesex County, New Jersey
and
City of Linden, Union County, New Jersey

LEAD AGENCY
U.S. COAST GUARD
COOPERATING AGENCY
U.S. ARMY CORPS OF ENGINEERS

SEPTEMBER 2008

Submitted by:
NEW JERSEY TURNPIKE AUTHORITY

Prepared for:
JACOBS EDWARDS & KELCEY

Prepared by:
PAULUS, SOKOLOWSKI & SARTOR, LLC
Consulting Engineers and Environmental Planners
Warren, Somerset County, New Jersey

TABLE OF CONTENTS

	<u>Page No.</u>
EXECUTIVE SUMMARY	ES-1
1.0 SUMMARY OF THE PROJECT	1-1
1.1 Project Location and Description.....	1-1
1.2 Project Purpose and Need	1-1
1.3 Wetlands Impacts.....	1-6
1.4 Construction Impacts	1-7
1.5 Traffic	1-7
1.6 Air Quality	1-8
1.7 Alternative Alignments	1-8
1.8 Mitigation Measures	1-10
1.8.1 Temporary/Construction	1-10
1.8.2 Permanent/Operational	1-10
1.9 Unavoidable Adverse Environmental Impacts	1-11
1.10 Other Environmental Impacts	1-11
1.11 Licenses, Permits and Other Approvals.....	1-12
1.12 NEPA/Environmental Compliance.....	1-12
2.0 PURPOSE AND NEED AND DESCRIPTION OF THE PROPOSED PROJECT.....	2-1
2.1 Project History	2-1
2.2 Purpose and Need for the Project.....	2-3
2.2.1 Port of New York and New Jersey	2-3
2.2.2 Tremley Point.....	2-4
2.2.3 Constituency to be Served	2-5
2.2.4 Benefits of the Project.....	2-6
2.3 Project Description.....	2-7
2.4 Tremley Point Connector Road – Alternate 10.....	2-7
2.4.1 Description.....	2-7
2.4.2 Geometry.....	2-9
2.4.3 Environmental Impacts	2-9
2.4.4 Construction Cost.....	2-10
2.4.5 Advantages.....	2-10
2.4.6 Disadvantages	2-10
2.5 Project Sponsor	2-10
2.6 Project Setting	2-11
2.6.1 Regional	2-11
2.6.2 Municipal	2-11
2.6.3 Neighborhood	2-11
2.7 Design and Operational Features	2-11
2.7.1 Proposed Improvements.....	2-11
2.7.1.1 Construction Schedule	2-12
2.7.1.2 Work Force Required.....	2-12

2.7.1.3	Construction Traffic	2-12
2.7.1.4	Site Preparation	2-12
2.7.1.5	Precautionary Measures	2-12
2.7.2	Operational Phase	2-13
2.7.2.1	Capacity of Tremley Point Connector Road	2-13
2.7.2.2	Discharges	2-13
2.7.2.3	Use of Resources	2-13
3.0	ALTERNATIVES TO THE PROPOSED PROJECT	3-1
3.1	No-Action Alternative	3-3
3.2	Tremley Point Connector Road (TPCR) Alignment Alternatives	3-3
3.3	Tremley Point Connector Road - Alternate 1	3-4
3.3.1	Description	3-4
3.3.2	Geometry	3-6
3.3.3	Environmental and Security Impacts	3-6
3.3.4	Construction Cost	3-7
3.3.5	Advantages	3-7
3.3.6	Disadvantages	3-7
3.4	Tremley Point Connector Road - Alternate 2	3-8
3.4.1	Description	3-8
3.4.2	Geometry	3-8
3.4.3	Environmental Impacts	3-10
3.4.4	Construction Cost	3-10
3.4.5	Advantages	3-11
3.4.6	Disadvantages	3-11
3.5	Tremley Point Connector Road - Alternate 3	3-11
3.5.1	Description	3-11
3.5.2	Geometry	3-13
3.5.3	Environmental Impacts	3-13
3.5.4	Construction Cost	3-13
3.5.5	Advantages	3-14
3.5.6	Disadvantages	3-14
3.6	Tremley Point Connector Road - Alternate 4	3-14
3.6.1	Description	3-14
3.6.2	Geometry	3-14
3.6.3	Environmental Impacts	3-16
3.6.4	Construction Cost	3-16
3.6.5	Advantages	3-16
3.6.6	Disadvantages	3-16
3.7	Tremley Point Connector Road - Alternate 5	3-17
3.7.1	Description	3-17
3.7.2	Geometry	3-17
3.7.3	Environmental Impacts	3-19
3.7.4	Construction Cost	3-19
3.7.5	Advantages	3-20
3.7.6	Disadvantages	3-20
3.8	Tremley Point Connector Road - Alternate 6	3-20

3.8.1	Description.....	3-20
3.8.2	Geometry.....	3-22
3.8.3	Environmental Impacts	3-22
3.8.4	Construction Cost.....	3-22
3.8.5	Advantages.....	3-22
3.8.6	Disadvantages	3-23
3.9	Tremley Point Connector Road - Alternate 7	3-23
3.9.1	Description	3-23
3.9.2	Geometry.....	3-23
3.9.3	Environmental Impacts	3-25
3.9.4	Construction Cost.....	3-25
3.9.5	Advantages.....	3-25
3.9.6	Disadvantages	3-25
3.10	Tremley Point Connector Road – Alternate 8.....	3-26
3.10.1	Description.....	3-26
3.10.2	Geometry.....	3-26
3.10.3	Environmental Impacts	3-26
3.10.4	Construction Cost.....	3-28
3.10.5	Advantages.....	3-28
3.10.6	Disadvantages	3-28
3.11	Tremley Point Connector Road – Alternate 9.....	3-29
3.11.1	Description.....	3-29
3.11.2	Geometry.....	3-29
3.11.3	Environmental Impacts	3-29
3.11.4	Construction Cost.....	3-31
3.11.5	Advantages.....	3-31
3.11.6	Disadvantages	3-31
3.12	Location Alternatives.....	3-32
3.13	Alternative Constraints	3-32
3.14	Alternatives Evaluation Summary	3-34
3.14.1	Non-Viable Alternative Alignments	3-35
3.14.2	Viable Alternative Alignments	3-36
3.14.3	Conclusion	3-36
4.0	EXISTING CONDITIONS.....	4-1
4.1	Natural Resources	4-1
4.1.1	Geology.....	4-1
4.1.2	Soils.....	4-1
4.1.2.1	Regional Description.....	4-1
4.1.2.2	Geotechnical Borings	4-3
4.1.3	Land Form.....	4-4
4.1.4	Hydrological Features.....	4-4
4.1.4.1	Surface Water.....	4-4
4.1.4.2	Groundwater.....	4-7
4.1.4.3	Water Quality	4-7
4.1.4.4	Floodplain	4-8
4.1.4.5	Wetlands.....	4-8

4.1.5	Biological Features	4-13
4.1.5.1	Vegetation	4-13
4.1.5.2	Wildlife Habitat.....	4-15
4.1.5.3	Threatened or Endangered Species	4-23
4.1.6	Traffic	4-23
4.1.6.1	Tremley Point Connector Road.....	4-23
4.1.6.2	South Wood Avenue/Roosevelt Avenue.....	4-24
4.1.6.3	Model Development and Calibration	4-24
4.1.7	Noise	4-28
4.1.7.1	Noise Monitoring Equipment.....	4-28
4.1.7.2	Noise Monitoring Methodology.....	4-28
4.1.7.3	Noise Monitoring Locations	4-29
4.1.7.4	Noise Monitoring Results	4-30
4.1.8	Air Quality	4-32
4.1.8.1	North Jersey Transportation Improvement Program.	4-32
4.1.8.2	Air Pollutants and Ambient Air Quality Standards ..	4-32
4.1.9	Hazardous Materials	4-35
4.1.9.1	Database Search	4-35
4.1.9.2	Tesco Terminal, Linden	4-35
4.1.9.3	Tremley Point Industries, 4700 Tremley Point Road, Linden	4-36
4.1.9.4	Citgo Petroleum, 4801 Tremley Point Road, Linden	4-36
4.1.9.5	Cytec (American Cyanamid Warners Plant), 4900 Tremley Point Road, Linden	4-37
4.1.9.6	Cytec (American Cyanamid) Carteret Impoundments, Carteret.....	4-39
4.1.9.7	American Oil Company (BP/Amoco), 760 Roosevelt, Carteret.....	4-41
4.1.9.8	Kinder Morgan Inc. (former Philips Petroleum and General American Transport Corp. (GATX)) 78 Lafayette Street, Carteret	4-42
4.1.9.9	Titan PDC (Former Carteret Borough Sanitary), Roosevelt Avenue and Driftway Street, Carteret.....	4-43
4.1.9.10	Borough of Carteret, Block 11.1, Lots 6, 7, 18 and 19, Carteret	4-44
4.1.9.11	Industrial Highway.....	4-44
4.1.9.12	Environmental Sampling.....	4-45
4.1.9.12.1	Introduction	4-45
4.1.9.12.2	Remedial Investigation Work Plan	4-45
4.1.9.12.3	Implementation.....	4-46
4.1.9.12.4	Findings	4-46
4.2	Relationship of Project to Other Plans.....	4-47
4.2.1	New Jersey State Development and Redevelopment Plan	4-47
4.2.2	Union County Master Plan.....	4-48
4.2.3	Port Authority of New York and New Jersey Portfields Initiative	4-48

4.3	4.2.4 Smart Growth.....	4-49
	Man-Made Resources	4-51
	4.3.1 Project Site Land Use.....	4-51
	4.3.2 Adjacent Land Uses	4-51
	4.3.2.1 Borough of Carteret.....	4-51
	4.3.2.2 City of Linden	4-51
	4.3.3 Zoning	4-51
	4.3.3.1 Borough of Carteret.....	4-51
	4.3.3.2 City of Linden	4-51
	4.3.4 Population Density.....	4-51
	4.3.4.1 Existing Conditions.....	4-51
	4.3.5 Demographics	4-51
	4.3.6 Cultural Features	4-51
	4.3.7 Parks and Recreational Facilities	4-51
	4.3.8 Aesthetic Features.....	4-51
	4.3.9 Historic and Archeological Resources.....	4-51
	4.3.9.1 Area History	4-51
	4.3.9.2 Geology and Prehistoric Considerations.....	4-51
	4.3.10 Navigation.....	4-51
5.0	PROBABLE ENVIRONMENTAL IMPACT OF THE PROJECT	
	IF IMPLEMENTED	5-51
5.1	Natural Resources	5-51
	5.1.1 Geology.....	5-51
	5.1.2 Soils.....	5-51
	5.1.3 Land Form.....	5-51
	5.1.4 Hydrological Features	5-51
	5.1.4.1 Surface Water.....	5-51
	5.1.4.2 Groundwater.....	5-51
	5.1.4.3 Water Quality	5-51
	5.1.4.4 Floodplain	5-51
	5.1.4.5 Wetlands.....	5-51
	5.1.5 Biological Features	5-51
	5.1.5.1 Vegetation	5-51
	5.1.5.2 Wildlife Habitat.....	5-51
	5.1.5.3 Threatened and Endangered Species.....	5-51
	5.1.6 Traffic	5-51
	5.1.6.1 TPCR.....	5-51
	5.1.6.2 Roosevelt Avenue – Carteret	5-51
	5.1.6.3 South Wood Avenue - Linden.....	5-51
	5.1.6.4 Existing, Approved and Proposed Traffic.....	5-51
	5.1.6.5 South Wood Avenue Roadway Capacity	5-51
	5.1.6.6 South Wood Avenue Vehicle Travel	5-51
	5.1.7 Noise	5-51
	5.1.8 Air Quality	5-51
	5.1.9 Hazardous Materials	5-51

5.2	Man-Made Resources	5-51
5.2.1	Land Use	5-51
5.2.2	Secondary Impact Area Land Uses.....	5-51
5.2.3	Zoning.....	5-51
5.2.4	Population Density.....	5-51
5.2.5	Demographics	5-51
5.2.6	Public and Municipal Services.....	5-51
5.2.7	Utilities.....	5-51
5.2.8	Navigation.....	5-51
5.3	Human Resources	5-51
5.3.1	Cultural Features.....	5-51
5.3.2	Parks and Recreational Facilities.....	5-51
5.3.3	Aesthetic Features	5-51
5.3.4	Historic Resources	5-51
5.3.5	Archeological Resources	5-51
5.3.6	Environmental Justice.....	5-51
6.0	METHODS OF MITIGATING ADVERSE ENVIRONMENTAL IMPACTS	6-51
6.1	Short Term Impacts.....	6-51
6.1.1	Soils.....	6-51
6.1.2	Air Quality	6-51
6.1.3	Noise	6-51
6.1.4	Hazardous Materials	6-51
6.1.5	Traffic	6-51
6.1.6	Historic and Archaeological Resources	6-51
6.2	Long-Term Impacts	6-51
6.2.1	Water Quality.....	6-51
6.2.2	Wetlands	6-51
6.2.3	Wetlands Findings	6-51
6.2.4	Air Quality	6-51
6.2.5	Noise	6-51
6.2.6	Traffic	6-51
6.2.6.1	Opening year (2010) Traffic Mitigation	6-51
6.2.6.2	Future year (2029) Traffic Mitigation.....	6-51
7.0	AVOIDANCE OF ADVERSE ENVIRONMENTAL IMPACTS	7-51
8.0	REFERENCES	8-51

	<u>Page No.</u>
Figure No. ES-1	Access Alternatives from NJ Turnpike to Tremley Point.....ES-2
Figure No. 1	Site Location Map.....1-2
Figure No. 2	Road Map.....1-3
Figure No. 3	Adjacent Properties to Project Area.....1-4
Figure No. 4	Tremley Point Connector Road Alternate 10.....2-8
Figure No. 5	Tremley Point Connector Road Alternate 1.....3-5
Figure No. 6	Tremley Point Connector Road Alternate 2.....3-9
Figure No. 7	Tremley Point Connector Road Alternate 3.....3-12
Figure No. 8	Tremley Point Connector Road Alternate 4.....3-15
Figure No. 9	Tremley Point Connector Road Alternate 5.....3-18
Figure No. 10	Tremley Point Connector Road Alternate 6.....3-21
Figure No. 11	Tremley Point Connector Road Alternate 7.....3-23
Figure No. 12	Tremley Point Connector Road Alternate 8.....3-26
Figure No. 13	Tremley Point Connector Road Alternate 9.....3-29
Figure No. 14	Soils Map4-2
Figure No. 15	Surface Water Bodies4-5
Figure No. 16	Federal Emergency Management Agency Flood Plain Map4-9
Figure No. 17	National Wetlands Inventory Map.....4-10
Figure No. 18	NJDEP Freshwater Wetlands Map4-11
Figure No. 19	Traffic Data Collection Locations4-23
Figure No. 20	Noise Monitoring Locations – Carteret and Linden4-29
Figure No. 21	Land Use Map.....4-51
Figure No. 22	Piles Creek Wetlands Mitigation Area5-4
Figure No. 23	Noise Modeling Results – Sensitive Receptors5-19
Figure No. 24	Noise Modeling Receptor Locations (Project Build).....5-20

Appendix H

Figure No. A	Interchange 12A – Alternate A3-2
Figure No. B	Interchange 12A – Alternate B3-5
Figure No. C	Interchange 12A – Alternate C3-8
Figure No. D	Interchange 12A – Alternate D3-11
Figure No. E	Interchange 12A – Alternate E3-13

List of Tables

Table 1-1	Summary of Alternatives for Tremley Point Connector Road
Table 3-1	Tremley Point Connector Road Alternatives Summary
Table 4-1	Amphibians and Reptiles Potentially Found in the Project Area
Table 4-2	Birds Potentially Found in the Project Area
Table 4-3	Mammals Potentially Found in the Project Area
Table 4-4	Fish Collected from the Arthur Kill
Table 4-5	Base Traffic Volumes
Table 4-6	Noise Monitoring Locations
Table 4-7	Noise Monitoring Results
Table 4-8	Background Ambient Air Data
Table 4-9	Population Density
Table 4-10	Ethnic Background of Population
Table 4-11	2000 Annual Labor Force Estimates
Table 4-12	Occupations of the Project Area Population
Table 4-13	Median Household Income
Table 4-14	Housing Profile
Table 4-15	Level of Education Attainment
Table 4-16	Means of Transportation to Work and Average Travel Time
Table 5-1	2009 Projected Traffic Volumes
Table 5-2	HCS Analysis Results
Table 5-3	Carteret Development Trips
Table 5-4	Tremley Point Expansion Trips
Table 5-5	Overall Traffic Impacts
Table 5-6	South Wood Avenue Model Assignment Comparison – Vehicle Mile and Vehicle Hour Summaries
Table 5-7	South Wood Avenue Model – Vehicle Hours of Travel and Vehicle Miles Traveled Comparison
Table 5-8	South Wood Avenue – (Between Route 1&9 and NJ Turnpike) – Vehicle Mile and Vehicle Hour Summaries
Table 5-9	South Wood Avenue – (Between Route 1&9 and NJ Turnpike) – Vehicle Hours Traveled and Vehicle Miles Traveled Comparison
Table 5-10	Noise Modeling Results Sensitive Receptors
Table 5-11	Environmental Impact Checklist

List of Appendices

Appendix A	Tremley Point Connector Road Traffic Analysis
Appendix B	Tremley Point Connector Road Mobile Source Noise Impact Assessment
Appendix C	Correspondence related to Project
Appendix D	NJDEP Natural Heritage Database
Appendix E	Remedial Investigation Report
Appendix F	Geotechnical Report
Appendix G	Navigation Study
Appendix H	Interchange 12A Alternatives Analysis
Appendix I	Essential Fish Habitat Analysis